

SPS Software Test Cases

PFS-SPS-PRU300005-01

Arnaud Le Fur, Hassan Siddiqui

October 17, 2019

Contents

1	Version and Changelog	6
2	Introduction	6
3	Test Case SPS-ALERT-TRIGGER-010: Alerts trigger mechanism	7
3.1	Description	7
3.2	Pass/Fail Condition(s)	7
3.3	Hardware constraints	7
3.4	Initial conditions	7
3.5	Procedure	7
3.6	Additional Notes	7
4	Test Case SPS-ALERT-INVALID-020: Alerts invalid values mechanism	8
4.1	Description	8
4.2	Pass/Fail Condition(s)	8
4.3	Hardware constraints	8
4.4	Initial conditions	8
4.5	Procedure	8
4.6	Additional Notes	8
5	Test Case SPS-ALERT-TIMEOUT-030: Alerts values out-of-date	9
5.1	Description	9
5.2	Pass/Fail Condition(s)	9
5.3	Hardware constraints	9
5.4	Initial conditions	9
5.5	Procedure	9
5.6	Additional Notes	9

6	Test Case SPS-XCU-PCM-040: Cryostat power control module	10
6.1	Description	10
6.2	Pass/Fail Condition(s)	10
6.3	Hardware constraints	10
6.4	Initial conditions	10
6.5	Procedure	10
6.6	Additional Notes	10
7	Test Case SPS-XCU-GATEVALVE-050: Cryostat Gatevalve	11
7.1	Description	11
7.2	Pass/Fail Condition(s)	11
7.3	Hardware constraints	11
7.4	Initial conditions	11
7.5	Procedure	11
7.6	Additional Notes	11
8	Test Case SPS-XCU-TURBO-060: Cryostat Turbo Pump	12
8.1	Description	12
8.2	Pass/Fail Condition(s)	12
8.3	Hardware constraints	12
8.4	Initial conditions	12
8.5	Procedure	12
8.6	Additional Notes	12
9	Test Case SPS-XCU-IONPUMP-070: Cryostat Ion Pumps	13
9.1	Description	13
9.2	Pass/Fail Condition(s)	13
9.3	Hardware constraints	13
9.4	Initial conditions	13
9.5	Procedure	13
9.6	Additional Notes	13
10	Test Case SPS-XCU-GAUGE-080: Cryostat Gauge	14
10.1	Description	14
10.2	Pass/Fail Condition(s)	14
10.3	Hardware constraints	14
10.4	Initial conditions	14
10.5	Procedure	14
10.6	Additional Notes	14
11	Test Case SPS-XCU-COOLER-090: Cryostat Cooler	15
11.1	Description	15
11.2	Pass/Fail Condition(s)	15
11.3	Hardware constraints	15
11.4	Initial conditions	15

11.5	Procedure	15
11.6	Additional Notes	15
12	Test Case SPS-XCU-TEMPS-100: Cryostat Temps	16
12.1	Description	16
12.2	Pass/Fail Condition(s)	16
12.3	Hardware constraints	16
12.4	Initial conditions	16
12.5	Procedure	16
12.6	Additional Notes	16
13	Test Case SPS-XCU-HEATERS-110: Cryostat Heaters	17
13.1	Description	17
13.2	Pass/Fail Condition(s)	17
13.3	Hardware constraints	17
13.4	Initial conditions	17
13.5	Procedure	17
13.6	Additional Notes	17
14	Test Case SPS-LOG-120: Process logging	18
14.1	Description	18
14.2	Pass/Fail Condition(s)	18
14.3	Hardware constraints	18
14.4	Initial conditions	18
14.5	Procedure	18
14.6	Additional Notes	18
15	Test Case SPS-IO-130: Test File I/O	19
15.1	Description	19
15.2	Pass/Fail Condition(s)	19
15.3	Hardware constraints	19
15.4	Initial conditions	19
15.5	Procedure	19
15.6	Additional Notes	19
16	Test Case SPS-BIAS-140: Detector Bias	20
16.1	Description	20
16.2	Pass/Fail Condition(s)	20
16.3	Hardware constraints	20
16.4	Initial conditions	20
16.5	Procedure	20
16.6	Additional Notes	20

17 Test Case SPS-DARK-150: Detector Dark	21
17.1 Description	21
17.2 Pass/Fail Condition(s)	21
17.3 Hardware constraints	21
17.4 Initial conditions	21
17.5 Procedure	21
17.6 Additional Notes	21
18 Test Case SPS-SHUTTER-160: Shutter control	22
18.1 Description	22
18.2 Pass/Fail Condition(s)	22
18.3 Hardware constraints	22
18.4 Initial conditions	22
18.5 Procedure	22
18.6 Additional Notes	22
19 Test Case SPS-SLIT-170: Slit movement	23
19.1 Description	23
19.2 Pass/Fail Condition(s)	23
19.3 Hardware constraints	23
19.4 Initial conditions	23
19.5 Procedure	23
19.6 Additional Notes	23
20 Test Case SPS-REXM-180: Red exchange mechanism movement	24
20.1 Description	24
20.2 Pass/Fail Condition(s)	24
20.3 Hardware constraints	24
20.4 Initial conditions	24
20.5 Procedure	24
20.6 Additional Notes	24
21 Test Case SPS-BIA-190: Check Back Illumination Assembly Photoresistance	25
21.1 Description	25
21.2 Pass/Fail Condition(s)	25
21.3 Hardware constraints	25
21.4 Initial conditions	25
21.5 Procedure	25
21.6 Additional Notes	25
22 Test Case SPS-TEMPS-200: Check SPS Temperature	26
22.1 Description	26
22.2 Pass/Fail Condition(s)	26
22.3 Hardware constraints	26

22.4 Initial conditions	26
22.5 Procedure	26
23 Test Case SPS-IIS-210: Check Internal Illumination Sources	27
23.1 Description	27
23.2 Pass/Fail Condition(s)	27
23.3 Hardware constraints	27
23.4 Initial conditions	27
23.5 Procedure	27
23.6 Additional Notes	27
Acronyms	28
Glossary	28

1 Version and Changelog

The version of this document is **0.2** .

Version	Date	Author	Description
0.2	2019-10-16	A Le Fur	Updated test cases
0.1	2019-07-10	H Siddiqui	First version

2 Introduction

This document describes the test cases used for demonstrating the validity of the software used for SPS commanding, prior to delivery of the SM1 module to Subaru at the end of 2019.

The intention is for these test cases to be run at during the summer of 2019. A report of the outcome would then be provided to the Project Office, who would then decide whether the software is of an adequate level for use at Subaru.

3 Test Case SPS-ALERT-TRIGGER-010: Alerts trigger mechanism

3.1 Description

Checks an expected alarm is raised using different alert mechanisms :

1. LIMITS ALERT : value within bounds.
2. REGEXP ALERT : regular expression.
3. Callback : dedicated python function.

Dedicated testsActor keywords are tracked by alertsActor. A command is sent to testsActor to generate out of range values and therefore trigger the alerts.

3.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

1. an expected alert is raised when all keytest1 values are not within 160-166
2. an expected alert is raised when keytest2 value is above 1.0e-6
3. an expected alert is raised when keytest3[1] is not "OK"

Fail no alerts are raised .

3.3 Hardware constraints

None.

3.4 Initial conditions

alertsActor and testsActor started

3.5 Procedure

1. AlertsActor : connect tests controller: `alerts connect controller=tests`
2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
3. TestsActor : trigger the alerts: `tests alerts trigger`
4. AlertsActor : disconnect tests controller: `alerts disconnect controller=tests`

3.6 Additional Notes

None.

4 Test Case SPS-ALERT-INVALID-020: Alerts invalid values mechanism

4.1 Description

Checks that an expected alarm is raised when an invalid value is generated. Since dedicated testsActor keywords are tracked by alertsActor, a command is sent to testsActor to generate invalid values and therefore trigger the alerts.

4.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

1. an expected alert is raised when at least one keytest1 field value is invalid
2. an expected alert is raised when keytest2 value is invalid

Fail no alerts are raised

4.3 Hardware constraints

None.

4.4 Initial conditions

alertsActor and testsActor started

4.5 Procedure

1. AlertsActor : connect tests controller: `alerts connect controller=tests`
2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
3. TestsActor : trigger the alerts: `tests alerts invalid`
4. AlertsActor : disconnect tests controller: `alerts disconnect controller=tests`

4.6 Additional Notes

None.

5 Test Case SPS-ALERT-TIMEOUT-030: Alerts values out-of-date

5.1 Description

Checks that an expected alarm is raised when keyword values are no longer generated with `TIMELIM=180 secs`. Since dedicated testsActor keywords are tracked by alertsActor, a command is sent to testsActor to stop to keyword generation and therefore trigger the alerts.

5.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

1. an expected TIMEOUT alert is raised after 180 seconds

Fail no alerts are raised

5.3 Hardware constraints

None.

5.4 Initial conditions

alertsActor and testsActor started

5.5 Procedure

1. AlertsActor : connect tests controller: `alerts connect controller=tests`
2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
3. TestsActor : trigger the alerts: `tests alerts timeout`
4. wait 180 seconds, keywords are no longer generated, alerts should be raised
5. AlertsActor : disconnect tests controller: `alerts disconnect controller=tests`

5.6 Additional Notes

None.

6 Test Case SPS-XCU-PCM-040: Cryostat power control module

6.1 Description

Check the communication with the PCM board of a given camera, check that the inputPower voltages and status are correct. Retrieve and generate volt, current, power for each PCM channel.

6.2 Pass/Fail Condition(s)

Pass PCM dataset will be generated and command should finish with ‘test=power-cam,OK’

Fail If an exception is raised ‘test=power-cam,FAILED’ will be generated with its full trace.

6.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.

6.4 Initial conditions

xcuActor and testsActor started

6.5 Procedure

1. testsActor : send power test command: `tests power cam=r1` .
2. wait for the command to end.

6.6 Additional Notes

None.

7 Test Case SPS-XCU-GATEVALVE-050: Cryostat Gatevalve

7.1 Description

Check the communication with the gatevalve of a given camera, check that the statuses are correct. Retrieve and generate gatevalve and interlock status.

7.2 Pass/Fail Condition(s)

Pass Gatevalve dataset will be generated and command should finish with `'test=gatevalve-cam,OK'`

Fail If an exception is raised `'test=gatevalve-cam,FAILED'` will be generated with its full trace.

7.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.

7.4 Initial conditions

xcuActor and testsActor started

7.5 Procedure

1. testsActor : send gatevalve test command: `tests gatevalve cam=r1` .
2. wait for the command to end.

7.6 Additional Notes

None.

8 Test Case SPS-XCU-TURBO-060: Cryostat Turbo Pump

8.1 Description

Check the communication with the turbo of a given camera, check that the statuses are correct. Retrieve and generate turbo telemetry.

8.2 Pass/Fail Condition(s)

Pass Turbo dataset will be generated and command should finish with ‘`test=turbo-cam,OK`’

Fail If an exception is raised ‘`test=turbo-cam,FAILED`’ will be generated with its full trace.

8.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.

8.4 Initial conditions

xcuActor and testsActor started

8.5 Procedure

1. testsActor : send turbo test command: `tests turbo cam=r1` .
2. wait for the command to end.

8.6 Additional Notes

None.

9 Test Case SPS-XCU-IONPUMP-070: Cryostat Ion Pumps

9.1 Description

Check the communication with the ionpumps of a given camera, check that the statuses are correct. Retrieve and generate ionpump state and telemetry.

9.2 Pass/Fail Condition(s)

Pass Ionpump dataset will be generated and command should finish with ‘test=ionpump-cam,OK’

Fail If an exception is raised ‘test=ionpump-cam,FAILED’ will be generated with its full trace.

9.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Ionpump controllers powered up.

9.4 Initial conditions

xcuActor and testsActor started

9.5 Procedure

1. testsActor : send ionpump test command: `tests ionpump cam=r1` .
2. wait for the command to end.

9.6 Additional Notes

None.

10 Test Case SPS-XCU-GAUGE-080: Cryostat Gauge

10.1 Description

Check the communication with the gauge of a given camera, check that the value is valid

10.2 Pass/Fail Condition(s)

Pass Gauge dataset will be generated and command should finish with `'test=gauge-cam,OK'`

Fail If the sensor reads NaN or zero or if an exception is raised `'test=gauge-cam,FAILED'` will be generated

10.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Gauge powered up.

10.4 Initial conditions

xcuActor and testsActor started

10.5 Procedure

1. testsActor : send gauge test command: `tests gauge cam=r1` .
2. wait for the command to end.

10.6 Additional Notes

None.

11 Test Case SPS-XCU-COOLER-090: Cryostat Cooler

11.1 Description

Check the communication with the cooler of a given camera, check that the statuses are correct. Retrieves and generates Cryocooler telemetry.

11.2 Pass/Fail Condition(s)

Pass Cooler dataset will be generated and command should finish with ‘`test=cooler-cam,OK`’

Fail If an exception is raised ‘`test=cooler-cam,FAILED`’ will be generated with its full trace.

11.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Cooler controller powered up.

11.4 Initial conditions

xcuActor and testsActor started

11.5 Procedure

1. testsActor : send cooler test command: `tests cooler cam=r1`.
2. wait for the command to end.

11.6 Additional Notes

None.

12 Test Case SPS-XCU-TEMPS-100: Cryostat Temps

12.1 Description

Check the communication with the temperature board of a given camera, check that the values are valids

12.2 Pass/Fail Condition(s)

Pass Temps dataset will be generated and command should finish with ‘test=temps-cam,OK’

Fail If a sensor reads NaN or zero or if an exception is raised ‘test=temps-cam,FAILED’ will be generated

12.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Temperature board powered up.

12.4 Initial conditions

xcuActor and testsActor started

12.5 Procedure

1. testsActor : send temps test command: `tests temps cam=r1` .
2. wait for the command to end.

12.6 Additional Notes

None.

13 Test Case SPS-XCU-HEATERS-110: Cryostat Heaters

13.1 Description

Check the communication with the heaters of a given camera, check that the statuses are correct.

13.2 Pass/Fail Condition(s)

Pass Heaters dataset will be generated and command should finish with ‘test=heaters-cam,OK’

Fail If an exception is raised ‘test=heaters-cam,FAILED’ will be generated with its full trace.

13.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Temperature board powered up.

13.4 Initial conditions

xcuActor and testsActor started

13.5 Procedure

1. testsActor : send heaters test command: `tests heaters cam=r1 .`
2. wait for the command to end.

13.6 Additional Notes

None.

14 Test Case SPS-LOG-120: Process logging

14.1 Description

Checks that logging is active for a typical process.

14.2 Pass/Fail Condition(s)

Pass Logging of INFO, FAIL and WARN messages are correctly written to the expected log file

Fail Any result otherwise.

14.3 Hardware constraints

None.

14.4 Initial conditions

/data and /software volumes are created.

14.5 Procedure

None.

Step	Description	Pass/FAIL	Comment
1	TBW		

14.6 Additional Notes

A test script installed in the /software folder would address this test effectively.

15 Test Case SPS-IO-130: Test File I/O

15.1 Description

Checks that data can be read and written from the input and output directories.

15.2 Pass/Fail Condition(s)

Pass Data can be written to and read from the `/data` volume, and software can be written to and read from the `/software` volume.

Fail Any result otherwise.

15.3 Hardware constraints

None.

15.4 Initial conditions

`/data` and `/software` volumes are created.

15.5 Procedure

For each volume:

Step	Description	Pass/FAIL	Comment
1	Create small files		
2	Read those files		
3	Copy those files to new locations within same volume and check that they are readable.		

15.6 Additional Notes

A test script installed in the `/software` folder would address this test effectively.

16 Test Case SPS-BIAS-140: Detector Bias

16.1 Description

Take a bias on a given detector, check that the file is created correctly and fits header critical keys are set. Check that `IMAGETYP==BIAS` and `exptime==0`

16.2 Pass/Fail Condition(s)

Pass filepath and fits header keys be generated and command should finish with `'test=bias-cam,OK'`

Fail If an exception is raised `'test=bias-cam,FAILED'` will be generated with its full trace.

16.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Fee powered up

16.4 Initial conditions

ccdActor and testsActor started

16.5 Procedure

1. testsActor : send bias test command: `tests bias cam=r1 .`
2. wait for the command to end.

16.6 Additional Notes

None.

17 Test Case SPS-DARK-150: Detector Dark

17.1 Description

Take a 10 seconds dark on a given detector, check that the file is created correctly and FITS header-critical keys are set. Check that `IMAGETYP==DARK` and `exptime==10`

17.2 Pass/Fail Condition(s)

Pass filepath and fits header keys be generated and command should finish with `'test=dark-cam,OK'`

Fail If an exception is raised `'test=dark-cam,FAILED'` will be generated with its full trace.

17.3 Hardware constraints

1. SPS RACK powered up
2. BEE powered up.
3. Fee powered up

17.4 Initial conditions

ccdActor and testsActor started

17.5 Procedure

1. testsActor : send dark test command: `tests dark cam=r1` .
2. wait for the command to end.

17.6 Additional Notes

None.

18 Test Case SPS-SHUTTER-160: Shutter control

18.1 Description

Check the communication with the shutters, check that the statuses are correct.

Check movement for each shutter :

Step	Description
1	Ask for a 5 seconds exposure
2	Check the exptime error is below 0.1 sec
3	Check that the transient time is below 1 sec

18.2 Pass/Fail Condition(s)

Pass Shutters open/close as expected, with the correct speed ‘test=shutters-smId,OK’

Fail If an exception is raised ‘test=shutters-smId,FAILED’ will be generated with its full trace.

18.3 Hardware constraints

Enu rack powered up and connected to the PFS network

18.4 Initial conditions

enuActor and testsActor started

18.5 Procedure

1. testsActor : send shutters test command: `tests shutters sm1` .
2. wait for the command to end.

18.6 Additional Notes

None.

19 Test Case SPS-SLIT-170: Slit movement

19.1 Description

Check the communication with the slit hexapod, check that the statuses are correct. Check slit movement such that the expected positions are reached:

1. for each position A, B, C, D, E, F:
 - (a) command slit to be moved to that position
 - (b) check whether the expected position is reached with total absolute error below 50 microns

Step	Description
1	Position A (1,0,0,0,0,0)
2	Position B (0,1,0,0,0,0)
3	Position C (0,0,1,0,0,0)
4	Position D (0,0,0,1,0,0)
5	Position E (0,0,0,0,1,0)
6	Position F (0,0,0,0,0,1)

19.2 Pass/Fail Condition(s)

Pass Slit movement as expected ‘test=slit-smId,OK’

Fail If an exception is raised ‘test=slit-smId,FAILED’ will be generated with its full trace.

19.3 Hardware constraints

Slit hexapod controller powered up and connected to the PFS network

19.4 Initial conditions

enuActor and testsActor started

19.5 Procedure

1. testsActor : send slit test command: `tests slit sm1` .
2. wait for the command to end.

19.6 Additional Notes

None.

20 Test Case SPS-REXM-180: Red exchange mechanism movement

20.1 Description

Check the communication with rexm motor controller, check that the statuses are correct.
Checks that the red exchange mechanism moves as expected:

1. for each position : low resolution, medium resolution
2. command rexm to be moved to that position
3. check whether the expected position is reached with a correct timing

Step	Description
1	Initialization, low position
2	Go to med position
3	Go back to low position

20.2 Pass/Fail Condition(s)

Pass Rexam movement as expected ‘`test=rexm-smId,OK`’

Fail If an exception is raised ‘`test=rexm-smId,FAILED`’ will be generated with its full trace.

20.3 Hardware constraints

Enu rack powered up and connected to the PFS network

20.4 Initial conditions

enuActor and testsActor started

20.5 Procedure

1. testsActor : send rexm test command: `tests rexm sm1 .`
2. wait for the command to end.

20.6 Additional Notes

None.

21 Test Case SPS-BIA-190: Check Back Illumination Assembly Photoresistance

21.1 Description

Check the communication with biasha board, check that the statuses are correct. Turn on the BIA and Check photoresistances values.

21.2 Pass/Fail Condition(s)

Pass The photoresistances are measured as expected. ‘test=bia-smId,OK’

Fail If an exception is raised ‘test=bia-smId,FAILED’ will be generated with its full trace.

21.3 Hardware constraints

Enu rack powered up and connected to the PFS network

21.4 Initial conditions

enuActor and testsActor started

21.5 Procedure

1. testsActor : send bia test command: `tests bia sm1 .`
2. wait for the command to end.

21.6 Additional Notes

None.

22 Test Case SPS-TEMPS-200: Check SPS Temperature

22.1 Description

Check the communication with the temperature controller, check that the values are valids

22.2 Pass/Fail Condition(s)

Pass Temps dataset will be generated and command should finish with ‘test=temps-smId,OK’

Fail If a sensor reads NaN or zero or if an exception is raised ‘test=temps-smId,FAILED’ will be generated

22.3 Hardware constraints

Temperature controller powered up and connected to the PFS network

22.4 Initial conditions

enuActor and testsActor started

22.5 Procedure

1. testsActor : send temps test command: `tests temps sm1 .`
2. wait for the command to end.

23 Test Case SPS-IIS-210: Check Internal Illumination Sources

23.1 Description

Turn on each lamp of Internal Illumination Sources and check its power consumption.

23.2 Pass/Fail Condition(s)

Pass The power consumption are measured as expected. `'test=iis-smId,OK'`

Fail If an exception is raised `'test=iis-smId,FAILED'` will be generated with its full trace.

23.3 Hardware constraints

Enu rack powered up and connected to the PFS network

23.4 Initial conditions

enuActor and testsActor started

23.5 Procedure

1. testsActor : send iis test command: `tests iis sm1 .`
2. wait for the command to end.

23.6 Additional Notes

None.

Acronyms

SPS Spectrograph System.

Glossary

Spectrograph System The software which commands cobra motions.