Contents

1	Version and Changelog	6
2	Introduction 2.1 References to the Operational Database in test cases	6
3	Test Case SPS-ALERT-TRIGGER-010: Alerts trigger mechanism 3.1 Description	77
4	Test Case SPS-ALERT-INVALID-020: Alerts invalid values mechanism 4.1 Description 4.2 Pass/Fail Condition(s) 4.3 Hardware constraints 4.4 Initial conditions 4.5 Procedure 4.6 Additional Notes	8 8 8 8 8
5	Test Case SPS-ALERT-TIMEOUT-030: Alerts values out-of-date 5.1 Description	()
6	Test Case SPS-XCU-PCM-040: Cryostat power control module 6.1 Description	10 10 10 10 10 10 10
7	Test Case SPS-XCU-GATEVALVE-050: Cryostat Gatevalve 7.1 Description	11 13 13 13 13 13 13

8	Test Case SPS-XCU-TURBO-060: Cryostat Turbo Pump	12
	B.1 Description	12
	8.2 Pass/Fail Condition(s)	12
	3.3 Hardware constraints	12
	3.4 Initial conditions	12
	8.5 Procedure	12
	3.6 Additional Notes	12
0	E + C CDC VCII IONDIIMD 070 C + + I D	10
9	Test Case SPS-XCU-IONPUMP-070: Cryostat Ion Pumps	13
	9.1 Description	13
	9.2 Pass/Fail Condition(s)	13
	9.3 Hardware constraints	13
	9.4 Initial conditions	13
	9.5 Procedure	13
	9.6 Additional Notes	13
10	Test Case SPS-XCU-GAUGE-080: Cryostat Gauge	14
10	10.1 Description	14
	10.2 Pass/Fail Condition(s)	14
	10.3 Hardware constraints	14
	10.4 Initial conditions	14
	10.5 Procedure	14
	10.6 Additional Notes	14
	10.0 Additional Notes	14
11	Test Case SPS-XCU-COOLER-090: Cryostat Cooler	15
	11.1 Description	15
	11.2 Pass/Fail Condition(s)	15
	11.3 Hardware constraints	15
	11.4 Initial conditions	15
	11.5 Procedure	15
	11.6 Additional Notes	15
19	Test Case SPS-XCU-TEMPS-100: Cryostat Temps	16
14	12.1 Description	16
	12.2 Pass/Fail Condition(s)	16
	12.2 Hardware constraints	16
	12.4 Initial conditions	16
	12.5 Procedure	16
	12.6 Additional Notes	16
	12.0 Additional Notes	10
13	Test Case SPS-XCU-HEATERS-110: Cryostat Heaters	17
	13.1 Description	17
	13.2 Pass/Fail Condition(s)	17
	13.3 Hardware constraints	17
	13.4 Initial conditions	17

	3.5 Procedure	17 17
14 T	Test Case SPS-LOG-120: Process logging	18
	4.1 Description	18
	4.2 Pass/Fail Condition(s)	18
	4.3 Hardware constraints	18
	4.4 Initial conditions	18
	4.5 Procedure	18
	4.6 Additional Notes	18
15 T	Test Case SPS-IO-130: Test File I/O	19
1	5.1 Description	19
	5.2 Pass/Fail Condition(s)	19
	5.3 Hardware constraints	19
1	5.4 Initial conditions	19
	5.5 Procedure	19
	5.6 Additional Notes	19
16 T	Test Case SPS-BIAS-140: Detector Bias	20
1	6.1 Description	20
	6.2 Pass/Fail Condition(s)	20
	6.3 Hardware constraints	20
1	6.4 Initial conditions	20
	6.5 Procedure	20
	6.6 Additional Notes	20
17 T	Test Case SPS-DARK-150: Detector Dark	21
1	7.1 Description	21
1	7.2 Pass/Fail Condition(s)	21
	7.3 Hardware constraints	21
1	7.4 Initial conditions	21
	7.5 Procedure	21
1	7.6 Additional Notes	21
18 T	Test Case SPS-ARC-155: Acquire arc exposure	22
1	8.1 Description	22
1	8.2 Pass/Fail Condition(s)	22
	8.3 Hardware constraints	22
	8.4 Initial conditions	22
	8.5 Procedure	22
	8.6 Additional Notes	22

	Test Case SPS-SHUTTER-160: Shutter control	23
	19.1 Description	23
	19.2 Pass/Fail Condition(s)	23
	19.3 Hardware constraints	23
	19.4 Initial conditions	23
	19.5 Procedure	23
	19.6 Additional Notes	$\frac{23}{23}$
20	Test Case SPS-SLIT-170: Slit movement	24
	20.1 Description	24
	20.2 Pass/Fail Condition(s)	24
	20.3 Hardware constraints	24
	20.4 Initial conditions	24
	20.5 Procedure	$\frac{1}{24}$
	20.6 Additional Notes	$\frac{1}{24}$
	20.0 114410101141 1101005	_ 1
21	Test Case SPS-REXM-180: Red exchange mechanism movement	25
	21.1 Description	25
	21.2 Pass/Fail Condition(s)	25
	21.3 Hardware constraints	$\frac{25}{25}$
	21.4 Initial conditions	$\frac{-5}{25}$
	21.5 Procedure	$\frac{25}{25}$
	21.6 Additional Notes	$\frac{25}{25}$
	21.0 114410101141 110005	20
22	2 Test Case SPS-BIA-190: Check Back Illumination Assembly Photoresis-	
	tance	26
	22.1 Description	26
	22.2 Pass/Fail Condition(s)	26
	22.3 Hardware constraints	26
	22.4 Initial conditions	$\frac{-6}{26}$
	22.5 Procedure	$\frac{-6}{26}$
	22.6 Additional Notes	$\frac{26}{26}$
	T I C COMPUNITATION OF THE TOTAL OF THE TOTA	97
23	S lest Case SPS-IEMPS-200: Check SPS lemperature	27
23	3 Test Case SPS-TEMPS-200: Check SPS Temperature 23.1 Description	27
23	23.1 Description	27
23	23.1 Description	27 27
23	23.1 Description	27 27 27
23	23.1 Description 23.2 Pass/Fail Condition(s) 23.3 Hardware constraints 23.4 Initial conditions	27 27 27 27
23	23.1 Description	27 27 27
	23.1 Description 23.2 Pass/Fail Condition(s) 23.3 Hardware constraints 23.4 Initial conditions	27 27 27 27
	23.1 Description 23.2 Pass/Fail Condition(s) 23.3 Hardware constraints 23.4 Initial conditions 23.5 Procedure 4 Test Case SPS-IIS-210: Check Internal Illumination Sources	27 27 27 27 27 28
	23.1 Description 23.2 Pass/Fail Condition(s) 23.3 Hardware constraints 23.4 Initial conditions 23.5 Procedure Test Case SPS-IIS-210: Check Internal Illumination Sources 24.1 Description	27 27 27 27 27 28 28
	23.1 Description 23.2 Pass/Fail Condition(s) 23.3 Hardware constraints 23.4 Initial conditions 23.5 Procedure 4 Test Case SPS-IIS-210: Check Internal Illumination Sources	27 27 27 27 27 28

24.5 Procedure	
Acronyms	29
Glossary	29

1 Version and Changelog

The version of this document is 0.1.

Version	Date	Author	Description
0.1	2020-04-14	H Siddiqui	First version

2 Introduction

This document describes the test cases used for demonstrating the validity of the ICS software used for SPS commanding.

These tests will be run following the conclusion of the SM1 AIT test campaign conducted by LAM at Subaru in early 2020, and after the SpS software has been migrated to the new infrastructure that makes use of the IIC and the operations database. The purpose is to validate that software migration, and to ensure that the necessary control of the SpS hardware is achieved following the migration.

2.1 References to the Operational Database in test cases

This document represents tests that cover both pre- and post-migration tests. For the post-migration testing, the operational database will be involved. Therefore, these test cases describe checks involving the operational database. As the operational database is not relevant for the *pre-migration* tests, references to the operational database in the test cases should be ignored.

3 Test Case SPS-ALERT-TRIGGER-010: Alerts trigger mechanism

3.1 Description

Checks an expected alarm is raised using different alert mechanisms:

- 1. LIMITS ALERT: value within bounds.
- 2. REGEXP ALERT: regular expression.
- 3. Callback: dedicated python function.

Dedicated testsActor keywords are tracked by alertsActor. A command is sent to tests-Actor to generate out of range values and therefore trigger the alerts.

3.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

- 1. an expected alert is raised when all keytest1 values are not within 160-166
- 2. an expected alert is raised when keytest2 value is above 1.0e-6
- 3. an expected alert is raised when keytest3[1] is not "OK"

Fail no alerts are raised.

3.3 Hardware constraints

None.

3.4 Initial conditions

alertsActor and testsActor started

3.5 Procedure

- 1. AlertsActor: connect tests controller: alerts connect controller=tests
- 2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
- 3. TestsActor: trigger the alerts: tests alerts trigger
- 4. AlertsActor: disconnect tests controller: alerts disconnect controller=tests

3.6 Additional Notes

4 Test Case SPS-ALERT-INVALID-020: Alerts invalid values mechanism

4.1 Description

Checks that an expected alarm is raised when an invalid value is generated. Since dedicated testsActor keywords are tracked by alertsActor, a command is sent to testsActor to generate invalid values and therefore trigger the alerts.

4.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

- 1. an expected alert is raised when at least one keytest1 field value is invalid
- 2. an expected alert is raised when keytest2 value is invalid

Fail no alerts are raised

4.3 Hardware constraints

None.

4.4 Initial conditions

alertsActor and testsActor started

4.5 Procedure

- 1. AlertsActor: connect tests controller: alerts connect controller=tests
- 2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
- 3. TestsActor: trigger the alerts: tests alerts invalid
- 4. AlertsActor: disconnect tests controller: alerts disconnect controller=tests

4.6 Additional Notes

5 Test Case SPS-ALERT-TIMEOUT-030: Alerts values out-of-date

5.1 Description

Checks that an expected alarm is raised when keyword values are no longer generated with TIMELIM=180 secs. Since dedicated testsActor keywords are tracked by alertsActor, a command is sent to testsActor to stop to keyword generation and therefore trigger the alerts.

5.2 Pass/Fail Condition(s)

Pass Expected alerts seen on STS server side and written to log when the alerts are triggered.

 $1.\,$ an expected TIMEOUT alert is raised after 180 seconds

Fail no alerts are raised

5.3 Hardware constraints

None.

5.4 Initial conditions

alertsActor and testsActor started

5.5 Procedure

- 1. AlertsActor: connect tests controller: alerts connect controller=tests
- 2. wait 30 seconds, keywords are generated within ranges, no alerts are raised yet
- 3. TestsActor: trigger the alerts: tests alerts timeout
- 4. wait 180 seconds, keywords are no longer generated, alerts should be raised
- 5. AlertsActor: disconnect tests controller: alerts disconnect controller=tests

5.6 Additional Notes

6 Test Case SPS-XCU-PCM-040: Cryostat power control module

6.1 Description

Check the communication with the PCM board of a given camera, check that the inputPower voltages and status are correct. Retrieve and generate volt, current, power for each PCM channel.

6.2 Pass/Fail Condition(s)

Pass PCM dataset will be generated and command should finish with 'test=power-cam, OK'

Fail If an exception is raised 'test=power-cam, FAILED' will be generated with its full trace.

6.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.

6.4 Initial conditions

xcuActor and testsActor started

6.5 Procedure

- 1. testsActor: send power test command: tests power cam=r1.
- 2. wait for the command to end.

6.6 Additional Notes

7 Test Case SPS-XCU-GATEVALVE-050: Cryostat Gatevalve

7.1 Description

Check the communication with the gatevalve of a given camera, check that the statuses are correct. Retrieve and generate gatevalve and interlock status.

7.2 Pass/Fail Condition(s)

Pass Gatevalve dataset will be generated and command should finish with 'test=gatevalve-cam, OK'

Fail If an exception is raised 'test=gatevalve-cam, FAILED' will be generated with its full trace.

7.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.

7.4 Initial conditions

xcuActor and testsActor started

7.5 Procedure

- 1. testsActor: send gatevalve test command: tests gatevalve cam=r1.
- 2. wait for the command to end.

7.6 Additional Notes

8 Test Case SPS-XCU-TURBO-060: Cryostat Turbo Pump

8.1 Description

Check the communication with the turbo of a given camera, check that the statuses are correct. Retrieve and generate turbo telemetry.

8.2 Pass/Fail Condition(s)

Pass Turbo dataset will be generated and command should finish with 'test=turbo-cam, OK'

Fail If an exception is raised 'test=turbo-cam, FAILED' will be generated with its full trace.

8.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.

8.4 Initial conditions

xcuActor and testsActor started

8.5 Procedure

- 1. testsActor: send turbo test command: tests turbo cam=r1.
- 2. wait for the command to end.

8.6 Additional Notes

9 Test Case SPS-XCU-IONPUMP-070: Cryostat Ion Pumps

9.1 Description

Check the communication with the ionpumps of a given camera, check that the statuses are correct. Retrieve and generate ionpump state and telemetry.

9.2 Pass/Fail Condition(s)

Pass Ionpump dataset will be generated and command should finish with 'test=ionpump-cam, OK'

Fail If an exception is raised 'test=ionpump-cam, FAILED' will be generated with its full trace.

9.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Ionpump controllers powered up.

9.4 Initial conditions

xcuActor and testsActor started

9.5 Procedure

- 1. testsActor: send ionpump test command: tests ionpump cam=r1.
- 2. wait for the command to end.

9.6 Additional Notes

10 Test Case SPS-XCU-GAUGE-080: Cryostat Gauge

10.1 Description

Check the communication with the gauge of a given camera, check that the value is valid

10.2 Pass/Fail Condition(s)

Pass Gauge dataset will be generated and command should finish with 'test=gauge-cam, OK'

Fail If the sensor reads NaN or zero or if an exception is raised 'test=gauge-cam, FAILED' will be generated

10.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Gauge powered up.

10.4 Initial conditions

xcuActor and testsActor started

10.5 Procedure

- 1. testsActor: send gauge test command: tests gauge cam=r1.
- 2. wait for the command to end.

10.6 Additional Notes

11 Test Case SPS-XCU-COOLER-090: Cryostat Cooler

11.1 Description

Check the communication with the cooler of a given camera, check that the statuses are correct. Retrieves and generates Cryocooler telemetry.

11.2 Pass/Fail Condition(s)

Pass Cooler dataset will be generated and command should finish with 'test=cooler-cam,OK'

Fail If an exception is raised 'test=cooler-cam, FAILED' will be generated with its full trace.

11.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Cooler controller powered up.

11.4 Initial conditions

xcuActor and testsActor started

11.5 Procedure

- 1. testsActor: send cooler test command: tests cooler cam=r1.
- 2. wait for the command to end.

11.6 Additional Notes

12 Test Case SPS-XCU-TEMPS-100: Cryostat Temps

12.1 Description

Check the communication with the temperature board of a given camera, check that the values are valids

12.2 Pass/Fail Condition(s)

Pass Temps dataset will be generated and command should finish with 'test=temps-cam, OK'

Fail If a sensor reads NaN or zero or if an exception is raised 'test=temps-cam, FAILED' will be generated

12.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Temperature board powered up.

12.4 Initial conditions

xcuActor and testsActor started

12.5 Procedure

- 1. testsActor: send temps test command: tests temps cam=r1.
- 2. wait for the command to end.

12.6 Additional Notes

13 Test Case SPS-XCU-HEATERS-110: Cryostat Heaters

13.1 Description

Check the communication with the heaters of a given camera, check that the statuses are correct.

13.2 Pass/Fail Condition(s)

Pass Heaters dataset will be generated and command should finish with 'test=heaters-cam, OK'

Fail If an exception is raised 'test=heaters-cam, FAILED' will be generated with its full trace.

13.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Temperature board powered up.

13.4 Initial conditions

xcuActor and testsActor started

13.5 Procedure

- 1. testsActor: send heaters test command: tests heaters cam=r1.
- 2. wait for the command to end.

13.6 Additional Notes

14 Test Case SPS-LOG-120: Process logging

14.1 Description

Checks that logging is active for a typical process.

14.2 Pass/Fail Condition(s)

Pass Logging of INFO, FAIL and WARN messages are correctly written to the expected log file

Fail Any result otherwise.

14.3 Hardware constraints

None.

14.4 Initial conditions

/data and /software volumes are created.

14.5 Procedure

None.

Step	Description	Pass/FAIL	Comment
1	TBW		

14.6 Additional Notes

A test script installed in the /software folder would address this test effectively.

15 Test Case SPS-IO-130: Test File I/O

15.1 Description

Checks that data can be read and written from the input and output directories.

15.2 Pass/Fail Condition(s)

Pass Data can be written to and read from the /data volume, and software can be written to and read from the /software volume.

Fail Any result otherwise.

15.3 Hardware constraints

None.

15.4 Initial conditions

/data and /software volumes are created.

15.5 Procedure

For each volume:

Step	Description	Pass/FAIL	Comment
1	Create small files		
2	Read those files		
3	Copy those files to new lo-		
	cations within same volume		
	and check that they are		
	readable.		

15.6 Additional Notes

A test script installed in the /software folder would address this test effectively.

16 Test Case SPS-BIAS-140: Detector Bias

16.1 Description

Take a bias on a given detector, check that the file is created correctly and fits header critical keys are set. Check that IMAGETYP==BIAS and exptime==0

Check that the operations database is correctly populated.

16.2 Pass/Fail Condition(s)

Pass filepath and fits header keys be generated and command should finish with 'test=bias-cam,OK', and that the sps_exposure table is correctly populated, with the field pfs_visit_id set to the appropriate visit, exptime, set to 0 seconds, and the time_exp_start time_exp_end set such that they are equal.

Fail If an exception is raised 'test=bias-cam, FAILED' will be generated with its full trace, or that the operations database is not correctly populated.

16.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Fee powered up

16.4 Initial conditions

ccdActor and testsActor started

16.5 Procedure

- 1. testsActor: send bias test command: tests bias cam=r1.
- 2. wait for the command to end.

16.6 Additional Notes

17 Test Case SPS-DARK-150: Detector Dark

17.1 Description

Take a 10 seconds dark on a given detector, check that the file is created correctly and FITS header-critical keys are set. Check that IMAGETYP==DARK and exptime==10 Check that the operations database is correctly populated.

17.2 Pass/Fail Condition(s)

Pass filepath and fits header keys be generated and command should finish with 'test=dark-cam,OK', and that the sps_exposure table is correctly populated, with the field pfs_visit_id set to the appropriate visit, exptime, set to the exposure time (10 seconds), and the time_exp_start time_exp_end set appropriately.

Fail If an exception is raised 'test=dark-cam, FAILED' will be generated with its full trace, or that the operations database is not correctly populated.

17.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Fee powered up

17.4 Initial conditions

ccdActor and testsActor started

17.5 Procedure

- 1. testsActor: send dark test command: tests dark cam=r1.
- 2. wait for the command to end.

17.6 Additional Notes

18 Test Case SPS-ARC-155: Acquire arc exposure

18.1 Description

Take a 15 second arc exposure on a given detector. Check that the file is created correctly and critical keys in the FITS header are set correctly. (Specifically, check that IMAGETYP==ARC and EXPTME==15)

Check that the operations database is correctly populated.

18.2 Pass/Fail Condition(s)

Pass filepath and fits header keys be generated and command should finish with 'test=arc-cam,OK', and that the sps_exposure table is correctly populated, with the field pfs_visit_id set to the appropriate visit, exptime, set to the exposure time (15 seconds), and the time_exp_start time_exp_end set appropriately.

Fail If an exception is raised 'test=arc-cam, FAILED' will be generated with its full trace, or that the operations database is not correctly populated.

18.3 Hardware constraints

- 1. SPS RACK powered up
- 2. BEE powered up.
- 3. Fee powered up

18.4 Initial conditions

ccdActor and testsActor started

18.5 Procedure

- 1. testsActor: send arc test command: tests arc cam=r1.
- 2. wait for the command to end.

18.6 Additional Notes

19 Test Case SPS-SHUTTER-160: Shutter control

19.1 Description

Check the communication with the shutters, check that the statuses are correct. Check movement for each shutter:

Step	Description	
1	Ask for a 5 seconds exposure	
2	Check the exptime error is below 0.1 sec	
3	Check that the transient time is below 1 sec	

Open each shutter and check BIA interlock.

19.2 Pass/Fail Condition(s)

Pass Shutters open/close as expected with the correct speed, turning BIA on is forbidden 'test=shutters-smId,OK'

Fail If an exception is raised 'test=shutters-smId, FAILED' will be generated with its full trace.

19.3 Hardware constraints

Enu rack powered up and connected to the PFS network

19.4 Initial conditions

enuActor and testsActor started

19.5 Procedure

- 1. testsActor: send shutters test command: tests shutters sm1.
- 2. wait for the command to end.

19.6 Additional Notes

20 Test Case SPS-SLIT-170: Slit movement

20.1 Description

Check the communication with the slit hexapod, check that the statuses are correct. Check slit movement such that the expected positions are reached:

- 1. for each position A, B, C, D, E, F:
 - (a) command slit to be moved to that position
 - (b) check whether the expected position is reached with total absolute error below 50 microns

Step	Description
1	Position A $(1,0,0,0,0,0)$
2	Position B $(0,1,0,0,0,0)$
3	Position C $(0,0,1,0,0,0)$
4	Position D $(0,0,0,1,0,0)$
5	Position E $(0,0,0,0,1,0)$
6	Position F $(0,0,0,0,0,1)$

20.2 Pass/Fail Condition(s)

Pass Slit movement as expected 'test=slit-smId,OK'

Fail If an exception is raised 'test=slit-smId, FAILED' will be generated with its full trace.

20.3 Hardware constraints

Slit hexapod controller powered up and connected to the PFS network

20.4 Initial conditions

enuActor and testsActor started

20.5 Procedure

- 1. testsActor: send slit test command: tests slit sm1.
- 2. wait for the command to end.

20.6 Additional Notes

21 Test Case SPS-REXM-180: Red exchange mechanism movement

21.1 Description

Check the communication with rexm motor controller, check that the statuses are correct. Checks that the red exchange mechanism moves as expected:

- 1. for each position: low resolution, medium resolution
- 2. command rexm to be moved to that position
- 3. check whether the expected position is reached with a correct timing

Step	Description	
1	Initialization, low position	
2	Go to med position	
3	Go back to low position	

21.2 Pass/Fail Condition(s)

Pass Rexm movement as expected 'test=rexm-smId,OK'

Fail If an exception is raised 'test=rexm-smId, FAILED' will be generated with its full trace.

21.3 Hardware constraints

Enu rack powered up and connected to the PFS network

21.4 Initial conditions

enuActor and testsActor started

21.5 Procedure

- 1. testsActor: send rexm test command: tests rexm sm1.
- 2. wait for the command to end.

21.6 Additional Notes

22 Test Case SPS-BIA-190: Check Back Illumination Assembly Photoresistance

22.1 Description

Check the communication with biasha board, check that the statuses are correct. Turn on the BIA, check photoresistances values and check shutters interlock.

22.2 Pass/Fail Condition(s)

Pass The photoresistances are measured as expected. opening any shutter is forbidden 'test=bia-smId,OK'

Fail If an exception is raised 'test=bia-smId, FAILED' will be generated with its full trace.

22.3 Hardware constraints

Enu rack powered up and connected to the PFS network

22.4 Initial conditions

enuActor and testsActor started

22.5 Procedure

- 1. testsActor: send bia test command: tests bia sm1.
- 2. wait for the command to end.

22.6 Additional Notes

23 Test Case SPS-TEMPS-200: Check SPS Temperature

23.1 Description

Check the communication with the temperature controller, check that the values are valids

23.2 Pass/Fail Condition(s)

Pass Temps dataset will be generated and command should finish with 'test=temps-smId,OK'

Fail If a sensor reads NaN or zero or if an exception is raised 'test=temps-smId, FAILED' will be generated

23.3 Hardware constraints

Temperature controller powered up and connected to the PFS network

23.4 Initial conditions

enuActor and testsActor started

23.5 Procedure

- 1. testsActor: send temps test command: tests temps sm1.
- 2. wait for the command to end.

24 Test Case SPS-IIS-210: Check Internal Illumination Sources

24.1 Description

Turn on each lamp of Internal Illumination Sources and check its power consumption.

24.2 Pass/Fail Condition(s)

Pass The power consumption are measured as expected. 'test=iis-smId,OK'

Fail If an exception is raised 'test=iis-smId, FAILED' will be generated with its full trace.

24.3 Hardware constraints

Enu rack powered up and connected to the PFS network

24.4 Initial conditions

enuActor and testsActor started

24.5 Procedure

- 1. testsActor: send iis test command: tests iis sm1.
- 2. wait for the command to end.

24.6 Additional Notes

Acronyms

BEE Back End Electronics.

ICS Instrument Control Software.

Glossary